

IFB 0929 VALENCIA ROAD BRIDGE

PREPARED FOR:

FAIRFIELD COUNTY, SOUTH CAROLINA

T&H PROJECT NO.
J-27466.0003

ADDENDUM NO. 2

September 21, 2020

GENERAL

This Addendum has been issued on behalf of Fairfield County, South Carolina. The following information should be considered by prospective bidders in preparation of their proposals and are hereby incorporated into the Proposal Documents. Bidders shall be responsible for acknowledging receipt of this addendum in the Bid Form, Document 00313. Failure to do so will result in the proposal being considered non-responsive.

PART I – CONTRACT DOCUMENTS

No changes

PART II – CONSTRUCTION PLANS

No changes

PART III – CLARIFICATIONS

The following are responses to Contractor questions:

1. Can the engineer provide any specifications regarding the profilograph? What type of profilograph equipment is required?

Contractor shall use a profilograph frame with between 6 and 12 wheels, such as the California or Rainhart Profilographs. If there is a question of adequacy, please submit for review and approval.

2. Is there a specified minimum tip for end bent piling?

The minimum tip is as shown on the drawings. We do not anticipate needing to modify the lengths of the piles.

3. How is the SWPPP to be paid?

Thomas & Hutton will be conducting the SWPPP inspections/reporting during the course of the project.

4. Note #3 states concrete washout areas must be located at least 50' from perimeter controls. This contradicts how the concrete washout areas are shown on sheet EC1.1. Which is the county's intent?

SCDHEC approved the plans; therefore, the location shown on the plans is acceptable instead of locating it 50' from the perimeter.

5. Sheet C3.1 shows type III barricades located in the roadway, while sheet C4.1 shows barricades permanently mounted on the shoulders. Which is the correct installation?

Note that the intent of the type III barricade is to be able to close the road access after each day's work. A Portable instead of permanent option is needed.

All other aspects of the project remain unchanged.

THOMAS & HUTTON

A handwritten signature in blue ink, appearing to read "M. Brad Sanderson". The signature is fluid and cursive, with the first name "M." and last name "Sanderson" clearly visible.

M. Brad Sanderson, P.E.
Project Manager

End of ADDENDUM NO. 2