ADDENDUM NO. 2
to
BIDDING/CONTRACT DOCUMENTS
for
RIVER ROAD FRE STATION PROJECT #19-72.08R1
IN
FAIRFIELD COUNTY, SOUTH CAROLINA

TO: All Prospective Bidders and Subcontractors DATE: August 29, 2022

DELIVERY: E-Mail & ICE file share site (Box)

This Addendum forms a part of the Contract Documents and modifies and /or clarifies the original Bidding Documents as noted below. **Acknowledge receipt of this Addendum in the space provided in the Proposal (Bid) Form.** Failure to do so may subject a Bidder to disqualification.

This Addendum consists of one (1) page and three (3) attachments.

I. GENERAL INFORMATION

1. Addenda Distribution: The addendum is provided to all known plan holders and interested parties who have contacted the Project Manager and is also posted at the same County Purchasing link previously provided for downloading the plans and specifications at: https://www.fairfieldsc.com/departments/purchasing/rfp-bids
2. Bidder Questions: The deadline for Bidder questions is noted in the "Request for Competitive Sealed Bids" was 10:00a.m. on Monday August 29, 2022. No further requests for contract or bid modifications can now be accepted.

II. PROJECT DRAWINGS

Refer to the attached revised plumbing drawings with clouded revisions. The changes are as follows:

1. Changed the 3 mop basins to 1 three bowl free standing sink and revised piping to match. Sheets P101, P102.
2. Added one floor sink at three bowl sink for drainage of three bowl sink. Sheets P101, P102
3. Added pipe sizes and "P" numbers at various places on the floor plans and on waste and water risers. Sheets P101, P102
4. Added backflow preventer detail to sheet P201
5. Revised plumbing fixture schedule to reflect floor plan changes and added floor sink, three bowl sink, and backflow preventer.
6. Revised layout of sheet P201 to fit backflow preventer detail.

Attachments- 1) Revised Plumbing Sheets P-101, P-102, and P-201 3 Sheets

END OF ADDENDUM NO. 2